SFUND RECORDS CTR 110298

Lockheed Martin Corporation Corporate Environment, Safety & Health West Coast Projects Office 2550 North Hollywood Way, 3rd Floor, Burbank, CA 91505-1055 Facsimile 818-847-0256 or 818-847-0170

LOCKHEED MARTIN

Via Courier RED0400/044 WBS #48

April 27, 2000

Mr. Gerard J. Thibeault Executive Officer California Regional Water Quality Control Board Santa Ana Region 3737 Main Street, Suite 500 Riverside, California 92501-3339

Dear Mr. Thibeault:

Subject: February 2000 Data Report

Water Supply Contingency Plan Production Well Sampling Program Crafton-Redlands Plume Project

In compliance with the approved Water Supply Contingency Plan, enclosed please find one copy of the **February 2000 Production Well Sampling Program** report prepared by HSI Geotrans for Lockheed Martin Corporation. This report presents analytical results from samples collected at Bunker Hill Basin Production Wells in February of 2000. Laboratory Quality Assurance/Quality Control documentation is included in Attachment B of the report.

Should you have any comments or requests, please contact me at (818) 847-0791.

Sincerely,

for: Thomas D. Blackman

Technical Project Manager

TDB:eah:mg

Enclosures

cc: See Attached Distribution List

Mr. Gerard Thibeault April 27, 2000 RED0400/044 Page 2

Distribution

cc: (Abbreviated Report Without Attachments "A & B" Which are Available Upon Request)

Kim Alexander, Psomas Engineering Chris Bahnsen, San Bernardino Valley Water Conservation District Kalyanpur Baliga, Department of Health Services (San Bernardino) Tom Crowley, San Bernardino Valley Water Conservation District Henry Dennis, Mountain View Power Co. Dodie Farmer, Victoria Farms Mutual Water Company Douglas Headrick, City of Redlands Ross Lewis, Gage Canal Company -Kevin Mayer, US EPA (Region IX) Steve Mains, Western Municipal Water District Morris Matson, Loma Linda University Eugene McMeans, Riverside Highland Water Company Zahra Panahi, City of Riverside Dan Randall, City of Riverside Bob Reiter, San Bernardino Valley Municipal Water District Toby Roy, Department of Health Services (San Diego) Jon Satrom, USAF, Norton Air Force Base Alain Sharp, Earth Technology Corporation Greg Snyder, City of Loma Linda

Joseph Stejskal, City of San Bernardino Dieter Wirtzfeld, City of Riverside

3150 Bristol Street Suite 500 Costa Mesa, California 92626

A TETRA TECH COMPANY

714-513-1415 FAX 714-513-1278

April 28, 2000

Lockheed Martin Corporation West Coast Project Office 2550 N. Hollywood Way, 3rd Floor Burbank, California 91505

Attention: Mr. Eric Hodder

Project Coordinator

Subject: February 2000 Data Report

Water Supply Contingency Plan Production Well Sampling Program Crafton-Redlands Plume Project

Dear Mr. Hodder:

This report presents a summary of results of the Water Supply Contingency Plan production well sampling for the month of February 2000. The Water Supply Contingency Plan (WSCP) was prepared by Lockheed Martin Corporation and submitted to the State of California Regional Water Quality Control Board (RWQCB) Santa Ana Region on September 30, 1996. The plan was conditionally approved by the RWQCB in a letter dated March 6, 1997. The WSCP for the Crafton-Redlands Plume was prepared to address maintenance of water supply to purveyors in the event that wells became impacted with trichloroethene (TCE) from the Crafton-Redlands TCE Plume. A summary of key dates and WSCP sampling program evolution is provided on Table 1.

The locations of the WSCP wells and analytical results for the February 2000 sampling event for TCE and perchlorate are shown on Figures 1 and 2, respectively. Table 2 presents a summary of analytical tests performed on each WSCP well and water system sampling point. The sampling frequency of each well is once a month for the first year. An alternate frequency, if required, is based on the analytical results as outlined in the WSCP TCE and perchlorate decision matrices, provided as Figures 3 and 4, respectively. The perchlorate decision matrix was presented in the *Perchlorate Work Plan and Schedule*, which was submitted, to the RWQCB on August 15, 1997. The RWQCB approved the

Perchlorate Work Plan on October 31, 1997. Table 3 presents a summary of the wells sampled twice monthly according to the decision matrices.

RESULTS

A summary of the analytical results for the February 2000 WSCP sampling event for TCE and perchlorate is shown on Figures 1 and 2, respectively, and presented on Table 4. Available groundwater elevation data is provided on Table 5. The water sampling field forms are provided in Attachment A. Chain-of-custody, laboratory data sheets, and Level III Modified laboratory quality assurance/quality control (QA/QC) documentation is provided in Attachment B.

Trichloroethene

Two groundwater samples collected in February met or exceeded $2/5^{th}$ the MCL for TCE (2.0 $\mu g/L$) including: COLL Mountain View #2 (3.2 $\mu g/L$), and COLL Richardson #1 (2.5 $\mu g/L$). Water from COLL Mountain View #2 and COLL Richardson #1 was not pumped into the system and therefore a confirmation sample was not collected.

The TCE observed at Gage 29-2 and Gage 29-3 is partially attributed to the Norton AFB plume and partially attributed to the Crafton Redlands plume, thus Gage 29-2 and Gage 29-3 are sampled twice a month for TCE when active. In February, Gage 29-2 and Gage 29-3 were off-line and not sampled.

The COLL Richardson Blend sampling point was not sampled in February because during the month of February, only the Richardson #3 well was pumping into the Richardson system. Thus, sampling of Richardson Blend was considered redundant.

Perchlorate

Groundwater samples collected from two wells in February met or exceeded 75 percent (13.5 μ g/L) of the PAL for perchlorate including: COLL Mountain View #2 (44 μ g/L), and COLL Richardson #1 (33 μ g/L). Water from COLL Mountain View #2 and COLL Richardson #1 was not pumped into the system and therefore confirmation samples were not collected.

Gage 29-2, Gage 29-3, Gage 51-1, Gage 92-1 and COLL Mountain View #2 wells are currently scheduled for sampling on a twice a month basis for perchlorate, if active. Gage 29-2, Gage 29-3, Gage 51-1, and Gage 92-1 were off-line in February and thus were not sampled.

The perchlorate impacts observed at COLL Mountain View #2 are consistent with historic data when the well has been idle and sampled shortly after the pump has turned on. The perchlorate impacts observed at Richardson #1 are a result of cross-flow between hydrostratigraphic units through Richardson #2. The Richardson #2 well was abandoned (San Bernardino County permitted well destruction) in February 2000.

CLOSING

HSI GeoTrans greatly appreciates being of continued service to Lockheed Martin Corporation on this project. Should you have any questions or comments, please do not hesitate to call.

Sincerely,

HSI GEOTRANS

Roy J. Marroquin Project Manager

James C. Norman, R.G., C.HG.

Project Director

TABLES

TABLE 1

KEY PROJECT DATES AND WSCP SAMPLING PROGRAM EVOLUTION

August 2, 1996, the RWQCB - Santa Ana Region requested Lockheed Martin to submit a conceptual Water Supply Contingency Plan.

September 30, 1996, Lockheed Martin submitted the Water Supply Contingency Plan (WSCP) to the RWQCB – Santa Ana Region.

March 6, 1997, the RWQCB conditionally approved the WSCP, which included sampling eight production wells (City of Loma Linda Richardson #1, Richardson #2, Mountain View #1, Mountain View #2, Victoria Farms Mutual Water Company Wells #1 and #3, and Southern California Edison #1 and #2).

June 1997, Victoria Farms Mutual Water Company was connected to City of San Bernardino Water. Pumping ceased at VFMWC #1 and #3, and the two wells were removed from the program.

June 1997, sampling of SCE #1 was discontinued because it is not operated on a regular basis. The WSCP consists of five wells, including COLL Mountain View #1 and #2, COLL Richardson #1 and #2, and SCE #2 (AUX).

August 1997, the WSCP was expanded due to the detection of perchlorate in municipal supply wells in the Bunker Hill Basin. Twenty-six wells were added to the WSCP including nineteen City of Riverside wells, five City of Redlands wells, and two Loma Linda University wells, for a total of 31 wells.

October 1997, three City of Riverside water system sampling points were added to the WSCP, including the Gage system pipeline (Gage Delivery), the Waterman system pipeline (Iowa Booster), and the sampling station measuring outflow from the Linden and Evans Reservoirs (7th & Chicago).

March 1998, two City of Loma Linda water system sampling points were added to the WSCP, including the Mountain View system pipeline (Mountain View Blend at Lawton) and the Richardson system pipeline (Richardson Blend).

June 1998, one City of Riverside irrigation water system sampling point (Gage Arlington) and one additional City of Loma Linda water system sampling point (Mountain View Blend at Timoteo) were added to the WSCP.

December 1998, the COLL Richardson #3 well was added to the WSCP Sampling Program.

May 1999, Sampling of Mountain View Blend at Timoteo was discontinued because it does not represent a blend sample of the Mountain View pipeline system.

December 1999, the COLL Mountain View #3 well and the Gage 98-1 well were added to the WSCP Sampling Program.

TABLE 2
WSCP PRODUCTION WELL SAMPLING PROGRAM

HSI#	Well Name	Perchlorate	TCE	
City of Loma	Linda	and the same of the same of		
692	Mountain View #2	X	X	
3106	Mountain View #3	X	X	
693	Richardson #1	X	X	
694	Richardson #2	X	X	
707	Richardson #3	Х	Х	
City of Loma	Linda Water System Sampling Point	S THE THE PARTY OF THE STATE OF		
2967	Mountain View Blend - Lawton	X	X	
2968	Richardson Blend	X	X	
Southern Cal	ifornia Edison			
554	SCF#2(AUX)	Χ	X	
Loma Linda l	Jniversity			
267	LLUniv Anderson #2	Χ		
717	LLUniv Anderson #3	X		
	ide (Gage System)			
252	Gage#26-1	X	Χ	
258	Gage#27-1	X	X	
259	Gage#27-2	X	X	
260	Gage#29-1	X	X	
219	Gage#29-2	X	X	
220	Gage#29-3	X	X	
218	Gage#30-1	X	X	
214	Gage#31-1	X	X	
215	Gage#46-1	X	X	
253	Gage#51-1	X	X	
216	Gage#56-1	X	X	
257	Gage#66-1	X	X	
644	Gage#92-1	X	X	
641	Gage#92-2	X	X	
642	Gage#92-3	X	X	
3091	Gage#98-1	X	X	
	ide (Waterman System)			
273	Hunt#6	X		
271	Hunt#10	X		
272	Hunt#11	X		
	ide Water System Sampling Points			
2946	Iowa Booster (Waterman)	X	X	
2947	Gage Delivery (Gage)	X	×	
2948	7th & Chicago (Reservoir)	X	$\frac{\lambda}{X}$	
3018	Gage Arlington	X		
City of Redla			Darring, Duracianos de la composición dela composición de la composición de la composición dela composición dela composición dela composición de la composición de la composición de la composición dela composición de la composición de la composición dela	
542	COR Church St	X		
2673	COR#38	X		
535	COR Mentone Acres	$\frac{\hat{x}}{\hat{x}}$		
	COR Orange st	X	*	
29 74	CORRees	$\frac{\hat{x}}{\hat{x}}$	X	
Notes:	CONNECS	^		

Notes:

TCE = Trichloroethene

Perchlorate analyzed using DHS Method (EPA 300.0 Modified)

TCE analyzed using EPA Method 502.2

TABLE 3

WSCP PRODUCTION WELL SAMPLING PROGRAM FEBRUARY 2000 WELLS SAMPLED TWICE MONTHLY

HSI#	Well Name	Perchlorate	TCE
City of Loma Linda			
692	Mountain View #2	x	
City of Riverside (Gage System)			
219	Gage #29-2	X	X
220	Gage #29-3	X	X
253	Gage #51-1	x	
644	Gage #92-1	X	

Notes:

TCE = Trichloroethene

Perchlorate analyzed using DHS Method (EPA 300.0 Modified).

TCE analyzed using EPA Method 502.2.

TABLE 4 WSCP PRODUCTION WELL SAMPLING PROGRAM FEBRUARY 2000 DATA RESULTS

HSI#	Well Name	Sample Date	Perchlorate (µg/L) Del Mar	TCE (µg/L) Del Mar		
City of Loma Lin	da		THE RESERVE OF THE			
692	Mountain View #2	2/1/00	44 ^c	3.2°		
692	Mountain View #2*	2/15/00	46 ^c	3.0°		
3106	Mountain View #3	2/1/00	ND(4)	ND(0.5)		
3106	MUN-769	2/1/00	ND(4)	ND(0.5)		
693	Richardson #1	2/1/00	33 ^{cd}	2.5 ^{cd}		
694	Richardson #2	NS	NS	NS		
707	Richardson #3	2/1/00	ND(4)	ND(0.5)		
	da Water System Sampling Points					
2967	Mountain View Blend-Lawton	2/1/00	ND(4)	ND(0.5)		
2968	Richardson Blend	NS	NS	NS		
Mountain View F	Power (Formerly Southern California	Edison)				
554	SCE#2(AUX)	2/1/00	ND(4)	ND(0.5)		
Loma Linda Univ						
267	LLUniv Anderson #2	2/1/00	ND(4)	NA		
717	LLUniv Anderson #3	2/1/00	ND(4)	NA NA		
	(Gage System)					
252	Gage#26-1 ^b	NS	NS I	NS		
258	Gage#27-1 ^b	NS	NS	NS		
259	Gage#27-1	NS NS	NS NS	NS NS		
260	Gage#29-1	NS NS	NS NS	NS NS		
219	Gage#29-2	NS NS	NS	NS NS		
219	Gage 29-2*	NS	NS NC	NS		
220	Gage#29-3	NS NS	NS NS	NS		
220	Gage#29-3*	NS	NS	NS		
218	Gage#30-1	NS	NS	NS NS		
214	Gage#31-1	NS NS	NS	NS NS		
215	Gage#46-1	NS NS	NS NS	NS NS		
253	Gage#51-1	NS	NS	NS		
253	Gage#51-1*	NS	NS	NA NA		
216 257	Gage#56-1 Gage#66-1	NS NS	NS NS	NS		
644		NS NC	NS NC	NS NS		
644	Gage#92-1	NS	NS NS	NS		
641	Gage#92-1*	NS 0/4/00		NA ND(0.5)		
	Gage#92-2	2/1/00	ND(4)	ND(0.5)		
642 3091	Gage#92-3	NS NS	NS NS	NS NS		
	Gage#98-1			NS		
	(Waterman System)					
273	Hunt#6 Hunt#10	NS NS	NS NS	NA NA		
271 272		NS NS	NS	NA NA		
	Hunt#11	NS	NS NS	NA		
	Water System Sampling Points	2/1/00	ND(4)			
	Iowa Booster (Waterman)			ND(0.5)		
2947	Gage Delivery (Gage)	2/1/00 2/1/00	ND(4)	ND(0.5)		
2948	7th & Chicago (Reservoir)		ND(4)	ND(0.5)		
	3018 Gage Arlington NS NS NA City of Redlands					
City of Redlands						
542	COR Church St ^a	NS	NS	NA NA		
2673	COR#38ª	NS	NS	NA		
535	COR Mentone Acres ^a	NS	NS	NA		
29	COR Orange St ^a	NS	NS	NA		
74	COR Rees	NS	NS	NS		

Notes:

= Twice-monthly sampling result

** = Confirmation sampling results
ND(4) = Not detected at the specified limit

MUN = Duplicate sample collected from the well listed directly above

NA = Not Analyzed
NS = Not Sampled

TCE = Trichloroethene

Perchlorate analyzed using DHS Method (EPA 300.0 Modified)

TCE analyzed using EPA Method 502.2

- = Well sampled on quarterly basis, if active
- = Gage 26-1 and Gage 27-1 are currently being treated for TCE
- c = Water purged to waste and not into system
- = Concentration in well is a result of cross flow between hydrostratigraphic units

TABLE 5

SUMMARY OF WATER LEVEL MEASUREMENTS FEBRUARY 2000 SAMPLING EVENT

HSI#	Well Name	Measure Date	Depth to Water	Measuring Point Elevation	Groundwater Elevation	Comments
	OMA LINDA	3	The second			Taring Same
692	Mountain View #2	01/31/00	143	1085	942	Static
3106	Mountain View #3	01/31/00	110	1086	976	Pumping
693	Richardson #1	01/31/00	121	1077	956	Static
694	Richardson #2	01/31/00	134	1078	944	Static
707	Richardson #3	01/31/00	185	1085	900	Pumping
Southern C	California Edison	j sa i arkitet	4 3 L V Z 190 4	A. THE PARTY NA	AND AND THE	
	SCE#2(AUX)	NM	NM	1100.00	NM	Pumping
	a University					
267	LLUniv Anderson #2	NM	NM	1075	NM	Pumping
·	LLUniv Anderson #3	NM	NM	1070	NM	Pumping
	erside (Gage System)	27 10 10 10 10 10 10	The second of th			Carl Carl Ma
252	Gage#26-1	02/01/00	86.20	1045.33	959.13	Pumping
258	Gage#27-1	02/01/00	84.90	1044.64	959.74	Pumping
259	Gage#27-2	02/01/00	69.80	1044.64	974.84	Static
260	Gage#29-1	02/01/00	70.90	1044.43	973.53	Static
219	Gage#29-2	02/01/00	63.90	1046.31	982.41	Static
220	Gage#29-3	02/01/00	69.00	1048.75	979.75	Static
218	Gage#30-1	02/01/00	87.10	1054.17	967.07	Static
214	Gage#31-1	02/01/00	68.10	1054.64	986.54	Static
215	Gage#46-1	02/01/00	73.30	1065.50	992.20	Static
253	Gage#51-1	02/01/00	75.30	1044.64	969.34	Static
216	Gage#56-1	02/01/00	114.70	1065.50	950.80	Static
257	Gage#66-1	02/01/00	76.80	1044.85	968.05	Static
644	Gage#92-1	02/01/00	100.90	1047.78	946.88	Static
641	Gage#92-2	02/01/00	155.00	1053.38	898.38	Pumping
642	Gage#92-3	02/01/00	159.70	1058.78	899.08	Pumping
3091	Gage#98-1	02/01/00	153.90	1058.78	904.88	Pumping
City of Riverside (Waterman System)						
273	Hunt#6	NM	NM	1015.5	NM	Pumping
271	Hunt#10	NM	NM	1017	NM	Pumping
272	Hunt#11	NM	NM	1015.7	NM	Pumping
City of Rec	City of Redlands					
542	COR Church St	Feb-00	147	1344.8	1197.8	Static
2673	COR#38	Feb-00	67	NA	NA	Static
535	COR Mentone Acres	Feb-00	239	1506.4	1267.4	Static
29	COR Orange st	Feb-00	110	1282	1172.0	Static
74	COR Rees	Feb-00	214	1490	1276.0	Static

Notes:

All measurements reported in feet below measuring point (ft-bmp)


Water level measurements for all City of Loma Linda, City of Riverside, and City of Redlands wells were obtained by purveyor personnel. Elevations given in feet above mean sea level (ft-msl)


NM=Not measured


NA=Data not available


Static water levels were allowed to recover a minimum of 30 minutes to obtain a static water level measurement

FIGURES









ATTACHMENT A
GEOLIS FIELD FORMS

ATTACHMENT A

GEOLIS FIELD FORMS (Available Upon Request)

ATTACHMENT B

CHAIN-OF-CUSTODY RECORDS AND
LABORATORY DATA SHEETS
QUALITY ASSURANCE/QUALITY CONTROL DOCUMENTATION

ATTACHMENT B

CHAIN-OF-CUSTODY RECORDS AND
LABORATORY DATA SHEETS AND LEVEL III MODIFIED
QUALITY ASSURANCE/QUALITY CONTROL DOCUMENTATION
(Available Upon Request)